Waihi Complex Significant Intersections Table

Hole Type	Hole	MGA Northing	MGA Easting	MGA RL	MGA Azimuth	Dip	Max Depth	From	To	Interval (m)	Grade (g/t)	Gram metre	Company
RCD	DRC144	6674495	271950	462	77	-60	80	36	38	2	73.88	147.8	CONSGOLD
DD	DRC240D	6674666	271815	464	77	-67	220	180	182	2	20.2	40.4	CONSGOLD
RC	DRC241D	6674857	271803	459	81	-62	247	150	159	9	4.63	41.67	CONSGOLD
RC	DRC301	6674657	271880	462	77	-70	125	87	91	4	23.4	93.6	CONSGOLD
RC	DRC323	6674686	271893	462	81	-65	95	85	92	7	7.7	53.9	CONSGOLD
RDC	DRC420D	6674301	272009	467	84	-59	210	109	139	30	18.46	553.8	CONSGOLD
RDC	DRC426D	6674354	272113	466	260	-62	165.5	124	138	14	12.99	181.9	CONSGOLD
RC	DRC431	6674827	271839	461	76	-68	155	118	129	11	4.5	49.5	CONSGOLD
RDC	DRC432D	6674433	271915	467	76	-70	343	90	98	8	10.69	85.5	CONSGOLD
RC	DRC447	6674581	271881	462	78	-60	140	110	115	5	42.8	214	CONSGOLD
RC	DRC479	6674854	271839	461	78	-65	137	58	67	9	12.81	115.29	CONSGOLD
RC	DRC488	6674629	271866	463	83	-62	161	142	149	7	7.19	50.3	CONSGOLD
RDC	DRC499D	6674240	272219	460	255	-56	156	127.6	133	5	10.76	53.8	DPPL
RCD	DRC500	6674296	272084	375	0	-90	51	0	44	44	4.55	200.2	DPPL
RDC	DVHC101	6674415	271983	463	90	-60	40	30	34	4	22.18	88.7	WMC
RDC	WHRC012	6674506	271948	452	76	-60	70	48	56	8	27.1	216.8	DPPL
RC	WHRC018	6674533	271953	454	76	-60	60	37	40	3	22.91	68.73	CROESUS
RC	WHRC029	6674942	271843	458	256	-62	100	93	95	2	18.21	36.4	CROESUS

Original assays are length weighted. Grades are not top cut. Lower cut is nominally 1g/t. Maximum 2m internal dilution.

ASX Date	Release Header
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex
22/02/2017	Impressive Results from Initial Drilling at Waihi Complex